

WAAS CH 61126 W22A	APP CRS 224°	Rwy Idg 5000 TDZE 1662 Apt Elev 1664
--	------------------------	---

RNAV (GPS) RWY 22

ROCKWOOD MUNI (RKW)

▼ For uncompensated Baro-VNAV systems, LNAV/VNAV NA below -18°C (0°F) or above 33°C (91°F). DME/DME RNP-0.3 NA. When local altimeter setting not received, use Crossville altimeter setting; increase LPV DA to 1987 feet and visibility all Cats ¼ SM; increase LNAV/VNAV DA to 2011 feet and visibility all Cats ¼ SM; increase all MDA 80 feet and increase LNAV Cat C and D visibility ¼ SM and Circling Cat C visibility ½ SM. Baro-VNAV NA when using Crossville altimeter setting.

MISSED APPROACH:
Climb to 5300 direct
CUTUK and hold,
continue climb-in-
hold to 5300.

AWOS-3 118.775	ATLANTA CENTER 133.6 254.3	UNICOM 122.8 (CTAF) 0
--------------------------	--------------------------------------	---------------------------------




Diagram illustrating the RW22 approach procedure. Key elements include:

- 5 NM Holding Pattern:** 044° outbound, 224° inbound, 5600 ft.
- Approach Path:** 224° to RW22, 1679 ft AGL, 5000 x 100 ft width, 0.6% UP slope.
- Altitudes:** 3500 ft (JUSTU), 4400 ft (USICU), 2100 ft (FEDOD).
- Distances:** 1.4 NM, 4.4 NM, 2.9 NM, 5.1 NM.
- Navigation:** VGS and RNAV glidepath not coincident (VGS Angle 3.00/TCH 31).