

SEDONA (SEZ)(KSEZ) 2 SW UTC-7 N34°50.92' W111°47.31'
4831 B TPA—See Remarks NOTAM FILE SEZ
RWY 03-21: H5132X100 (ASPH) S-15, D-30 MIRL 1.8% up NE
RWY 03: REIL. PAPI(P4L)—GA 3.0° TCH 44'.
RWY 21: REIL. PAPI(P4L)—GA 3.5° TCH 49'. Fence.
SERVICE: S2 **FUEL** 100LL, JET A **LGT** ACTVT REIL Rwy 03 and Rwy 21; PAPI Rwy 03 and Rwy 21; MIRL Rwy 03-21—CTAF. Rwy 21 PAPI unusbl byd 2.0 NM.

NOISE: Noise abatement proc in efct; scenic flt blw 6500 ft MSL na.
AIRPORT REMARKS: Attended May-Sep 1400-0100Z, Oct-Apr 1400-0000Z. Arpt on 500 ft mesa. Fuel ops til 30 min prior to closing; call out fee aft hr. Turb and wildlife on and invof arpt. TPA—prop 6004(1173) Jet 7004(2173). Rwy 03 calm wind rwy. Rwy 03 uphill slope. Rwy 21 lndg durg strong SW wind exp strong down draft NE of AOR. Lndg fee for turbine acft w/o fuel purchase. Overnight tnst fee.

AIRPORT MANAGER: 928-282-4487
WEATHER DATA SOURCES: AWOS-3PT 118.525 (928) 282-1993.
COMMUNICATIONS: CTAF/UNICOM 123.0
COTTONWOOD RCO 122.3 (PRESCOTT RADIO)

® **PHOENIX APP/DEP CON** 126.375
CLEARANCE DELIVERY PHONE: For CD ctc Phoenix Apch at 602-306-2565.
RADIO AIDS TO NAVIGATION: NOTAM FILE FLG.

FLAGSTAFF (VH) (DH) VOR/DME 113.85 FLG Chan 85(Y) N35°08.83' W111°40.45' 184° 18.8 NM to fld.
7026/14E.

VOR unusable:
030°-040° byd 40 NM
041°-051° byd 40 NM blo 18,000'
052°-061° byd 40 NM
062°-072° byd 40 NM blo 18,000'
073°-140° byd 40 NM
141°-151° byd 40 NM blo 18,000'
152°-159° byd 40 NM
160°-177° byd 40 NM blo 11,000'
160°-177° byd 48 NM blo 12,000'
160°-177° byd 63 NM
178°-231° byd 40 NM
232°-252° byd 40 NM blo 18,000'
253°-295° byd 40 NM
335°-030° byd 19 NM blo 24,000'
350°-026° byd 40 NM

DME unusable:
230°-255° byd 20 NM blo 15,000'

ASR/PAR

• • • • •
HELIPAD H1: H50X50 (CONC)

HELIPORT REMARKS: Rwy H1 flood lgts. HOP fm heli S and W of rwy; HOP rstrd to heli adj to twy intxn A7 SW main trml bldg.

