

**CRAIG-MOFFAT** (CAG)(KCAG) 2 SE UTC-7(-6DT) N40°29.71' W107°31.30'  
 6198 B NOTAM FILE CAG MON Airport  
**RWY 07-25:** H5606X100 (ASPH) S-35, D-40 PCN 12 F/D/X/T MIRL  
**RWY 07:** REIL. P-line.

**CHEYENNE**  
 H-3E, L-9E, 11E  
 IAP


**RWY 25:** REIL. PAPI(P4L)—GA 3.0° TCH 32'. Tree.  
**SERVICE:** FUEL 100LL, JET A LGT MIRL Rwy 07-25 preset low ints, to increase ints and ACTIVATE MIRL Rwy 07-25, REIL Rwy 07 and Rwy 25, and PAPI Rwy 25—CTAF.

**AIRPORT REMARKS:** Attended Mon-Fri 1500-0000Z Sat-Sun irregularly. Wildlife on and invof arpt. Rwy 25 has +10' road 340' from thld obstruction, +41' trees 1185' from thld 50' left of centerline, +75' trees 4000' from thld. Cold temperature airport. Altitude correction required at or below -31C.

**AIRPORT MANAGER:** 970-824-9148  
**WEATHER DATA SOURCES:** ASOS 135,425 (970) 824-2373.  
**COMMUNICATIONS:** CTAF/UNICOM 122.8

Ⓡ **DENVER CENTER APP/DEP CON** 120.475  
**CLEARANCE DELIVERY PHONE:** For CD etc Denver ARTCC at 303-651-4257.  
**RADIO AIDS TO NAVIGATION:** NOTAM FILE DEN.

**HAYDEN (VH) (H) VOR/DME** 115.6 CHE Chan 103 N40°31.20'  
 W107°18.29' 248° 10.0 NM to fld. 7271/14E.  
 VOR unusable:  
 036°-046° byd 40 NM blo 14,200'  
 036°-046° byd 49 NM  
 047°-070° byd 40 NM  
 071°-081° byd 40 NM blo 13,000'  
 071°-081° byd 60 NM  
 130°-208° byd 40 NM



**CRAWFORD** (99V) 2 W UTC-7(-6DT) N38°42.25' W107°38.62'  
 6470 TPA—7270(800) NOTAM FILE DEN  
**RWY 07-25:** H4900X20 (ASPH) LIRL(NSTD)  
**RWY 07:** VASI(NSTD). Trees.  
**RWY 25:** Hangar. Rgt tfc.  
**RWY E-W:** 2500X125 (TURF)  
**RWY E:** Rgt tfc.  
**RWY W:** Trees.

**DENVER**  
 L-9E

**SERVICE:** S2 LGT Arpt lgts opr dusk 0800Zt. Rwy 07 1 VASI box on left and right side of rwy. For local operators only or PPR call 970-921-7700. Rwy 07-25 has LIRL on N side on rwy for center 1600' beginning 1200' east of Rwy 07. No thld lgts. Rwy 07-25 3800' usable for ngt ops. Rwy 07-25 NSTD LIRL, Rwy 07-25 has LIRL only on north side on rwy for center 1600' beginning 1200 east of Rwy 07 thld. No thld lgts. Rwy 07-25 3800' usable for night opr. Rwy 07 NSTD VASI, has 1 VASI box on left and right side of rwy. For local opr only or PPR call 970-921-7700.

**AIRPORT REMARKS:** Attended continuously. Rwy 07-25 west 1300' only 25' wide. Glider ops invof arpt. Land to the east tkf to the west winds permitting. 100LL fuel avbl for emerg use only. Pedestrians, motor vehicles, deer and wildlife on and invof arpt. Unlimited vehicle use on arpt. Rwy West has +35' building 170' west of thld 30' left, +10' road 100' from thld centerline. +15' tree 150' from thld 0B. -8' to -20' terrain off both sides of first 674' of Rwy 25 end. E-W rwy consists of +12 inch alfalfa vegetation during various times of the year. Rwy 07 has 40' trees and -10' to -20' terrain 20' right of rwy first 150'. Rwy 25 has +20' trees 300' from thld 0B. Rwy 25 has 50' water tanks 900' from thld on extended centerline. +2' electric box 150' from thld 30' right. +10' road 100' from thld 0B. Rwy E has +20' trees at thld 150' right of centerline, +10' trees 150' from thld 0B.

**AIRPORT MANAGER:** 970-921-7700  
**COMMUNICATIONS:** CTAF/UNICOM 122.8

CONTINUED ON NEXT PAGE

## CONTINUED FROM PRECEDING PAGE

**CLEARANCE DELIVERY PHONE:** For CD ctc Denver ARTCC at 303-651-4257.

**RADIO AIDS TO NAVIGATION:** NOTAM FILE MTJ.

**MONTROSE (VH) (H) VORW/DME** 117.1 MTJ Chan 118 N38°30.39' W107°53.96' 033° 16.9 NM to fld.  
5713/12E. vDME unmonitored.

DME unusable:

011°-090° byd 26 NM blo 15,000'  
190°-250° byd 25 NM blo 15,000'

VOR unusable:

001°-167° byd 40 NM  
060°-090° byd 26 NM blo 16,000'  
167°-178° byd 50 NM  
168°-178° byd 40 NM blo 16,300'  
179°-251° byd 40 NM  
190°-250° byd 25 NM blo 15,000'  
252°-262° byd 40 NM blo 13,000'  
252°-262° byd 51 NM blo 15,500'  
252°-262° byd 72 NM  
263°-295° byd 40 NM  
313°-360° byd 40 NM

## CREEDE

**MINERAL CO MEML** (C24) 2 SSW UTC-7(-6DT) N37°49.33' W106°55.79'

DENVER  
H-3E, L-9E

8680 NOTAM FILE DEN

**RWY 07-25:** H6880X60 (ASPH) S-12.5

**RWY 07:** Thld dsplcd 188'.

**SERVICE:** FUEL 100LL, JET A

**AIRPORT REMARKS:** Unattended. Glider act and wildlife on and invof arpt. Mt all quad. Dep NE avoid overflight of trailers and homes, climb to +200 ft AGL on RCL bfr turn.

**AIRPORT MANAGER:** 719-658-2360

**COMMUNICATIONS:** CTAF 122.9

**CLEARANCE DELIVERY PHONE:** For CD ctc Denver ARTCC at 303-651-4257.

**RADIO AIDS TO NAVIGATION:** NOTAM FILE DEN.

**BLUE MESA (VH) (DH) VORW/DME** 114.9 HBU Chan 96 N38°27.13' W107°02.38' 158° 38.1 NM to fld.  
8740/14E.

DME unusable:

315°-325° byd 27 NM blo 17,500'

VOR unusable:

016°-026° byd 40 NM blo 17,500'  
027°-032° byd 40 NM  
033°-072° byd 40 NM blo 16,200'  
075°-085° byd 40 NM blo 16,000'  
075°-085° byd 58 NM  
086°-093° byd 40 NM  
098°-118° byd 40 NM  
119°-129° byd 40 NM blo 18,000'  
130°-187° byd 40 NM  
188°-198° byd 40 NM blo 18,000'  
199°-209° byd 40 NM  
210°-240° byd 40 NM blo 16,600'  
210°-240° byd 54 NM blo 18,000'  
210°-240° byd 59 NM blo 20,000'  
268°-274° byd 40 NM  
275°-285° byd 40 NM blo 14,000'  
275°-285° byd 50 NM  
286°-297° byd 40 NM blo 19,000'  
298°-015° byd 40 NM

## CUCHARA VALLEY AT LA VETA (See LA VETA on page 347)

**DAVIS FLD (USAF ACADEMY FLD)** (AFF)(KAFF) 10 N UTC-7(-6DT) N38°58.40' W104°49.20'

DENVER

Class D ATC svc avail dur afdl opr hr. Check AFF ATIS and NOTAMs for addn current info. Afdl official bus only. See L-10F

Special Notices—U.S. Air Force Academy.

**AIRSPACE:** CLASS D airspace SR-SS; other times CLASS G.