

DOUGLAS MUNI (DGL)(KDGL) 2 E UTC-7 N31°20.56' W109°30.39'
 4173 B AOE NOTAM FILE PRC
RWY 03-21: H5760X75 (ASPH) MIRL
RWY 03: PAPI(P4L)—GA 4.0° TCH 40'. Brush. Rgt tfc.
RWY 21: PAPI(P4L)—GA 4.0° TCH 50'. Brush.
RWY 18-36: 4095X100 (DIRT)

PHOENIX
H-4X, L-5D

RWY 18: Brush.
RWY 36: Brush. Rgt tfc.
SERVICE: FUEL 100LL, JET A LGT Dusk-dawn. PAPI Rwys 03 and 21
 OTS indfly.

AIRPORT REMARKS: Attended Mon-Fri 1300-2200Z, For svc after hours
 call 520-368-6015. Personnel on ATVs near acft opr
 areas-unrestricted. Mountains 1 1/2 miles east. 24 hr 100LL avbl
 with major credit card. Rwy 03-21 has 1"- 6" cracks across rwy. Rwy
 18-36 has +4' brush, rocks and uneven surface for 3/4 of rwy
 length. Rwy 21 50' twr 1350' from thld 550' left lgtd. Rwy 18-36
 brush on both sides 70 ft from centerline full length of rwy. Rwy
 18-36 surface rough and rutted. Rwy 18-36 +3 ft bump 300 ft from
 Rwy 18 thld. Rwy 18-36, 2 ft bump crossing twy to Rwy 03-21.
 Flight notification svc avbl.

AIRPORT MANAGER: (520) 368-6015

COMMUNICATIONS: CTAF/UNICOM 122.8

RCO 122.6 (PRESCOTT RADIO)

RADIO AIDS TO NAVIGATION: NOTAM FILE DUG.

(VL) (H) VORTACW 108.8 DUG Chan 25 N31°28.36' W109°36.12' 135° 9.2 NM to fld. 4131/13E.

TACAN AZIMUTH unusable:

- 045°-065° byd 26 NM blo 10,000'
- 065°-095° byd 28 NM blo 9,500'
- 355°-010° byd 35 NM blo 11,300'

DME unusable:

- 045°-065° byd 26 NM blo 10,000'
- 065°-095° byd 28 NM blo 9,500'
- 355°-010° byd 35 NM blo 11,300'

VOR unusable:

- 046°-063° byd 40 NM blo 11,000'
- 046°-063° byd 49 NM blo 16,000'
- 046°-063° byd 63 NM
- 253°-263° byd 40 NM blo 16,000'
- 253°-263° byd 66 NM
- 264°-277° byd 40 NM
- 278°-288° byd 40 NM blo 16,000'
- 278°-288° byd 52 NM
- 305°-316° byd 40 NM
- 345°-045° byd 40 NM

