

**CRAIG—MOFFAT** (CAG)(KCAG) 2 SE UTC-7(-6DT) N40°29.71' W107°31.30'  
 6198 B NOTAM FILE CAG MON Airport  
**RWY 07-25:** H5606X100 (ASPH) S-35, D-40 PCN 12 F/D/X/T MIRL  
**RWY 07:** REIL. P-line.

**CHEYENNE**  
 H-3E, L-9E, 11E  
 IAP


**RWY 25:** REIL. PAPI(P4L)—GA 3.0° TCH 32'. Tree.  
**SERVICE:** FUEL 100LL, JET A LGT MIRL Rwy 07-25 preset low ints, to increase ints and ACTIVATE MIRL Rwy 07-25, REIL Rwy 07 and Rwy 25, and PAPI Rwy 25—CTAF.

**AIRPORT REMARKS:** Attended Mon-Fri 1500-0000Z± Sat-Sun irregularly. Wildlife on and in/ov arpt. Rwy 25 has +10' road 340' from thld obstruction, +41' trees 1185' from thld 50' left of centerline, +75' trees 4000' from thld. Cold temperature airport. Altitude correction required at or below -31C.

**AIRPORT MANAGER:** 970-824-9148  
**WEATHER DATA SOURCES:** ASOS 135,425 (970) 824-2373.  
**COMMUNICATIONS:** CTAF/UNICOM 122.8

Ⓡ **DENVER CENTER APP/DEP CON** 120.475  
**CLEARANCE DELIVERY PHONE:** For CD etc Denver ARTCC at 303-651-4257.  
**RADIO AIDS TO NAVIGATION:** NOTAM FILE DEN.

**HAYDEN (VH) (H) VOR/DME** 115.6 CHE Chan 103 N40°31.20'  
 W107°18.29' 248° 10.0 NM to fld. 7271/14E.  
 VOR unusable:  
 036°-046° byd 40 NM blo 14,200'  
 036°-046° byd 49 NM  
 047°-070° byd 40 NM  
 071°-081° byd 40 NM blo 13,000'  
 071°-081° byd 60 NM  
 130°-208° byd 40 NM



**CRAWFORD** (99V) 2 W UTC-7(-6DT) N38°42.25' W107°38.62'  
 6470 TPA—7270(800) NOTAM FILE DEN  
**RWY 07-25:** H4900X20 (ASPH) LIRL(NSTD)  
**RWY 07:** VASI(NSTD). Trees.  
**RWY 25:** Hangar. Rgt tfc.  
**RWY E-W:** 2500X125 (TURF)  
**RWY E:** Rgt tfc.  
**RWY W:** Trees.

**DENVER**  
 L-9E

**SERVICE:** S2 LGT Arpt lgts opr dusk 0800Z±. Rwy 07 1 VASI box on left and right side of rwy. For local operators only or PPR call 970-921-7700. Rwy 07-25 has LIRL on N side on rwy for center 1600' beginning 1200' east of Rwy 07. No thld lgts. Rwy 07-25 3800' usable for ngt ops. Rwy 07-25 NSTD LIRL, Rwy 07-25 has LIRL only on north side on rwy for center 1600' beginning 1200 east of Rwy 07 thld. No thld lgts. Rwy 07-25 3800' usable for night opr. Rwy 07 NSTD VASI, has 1 VASI box on left and right side of rwy. For local opr only or PPR call 970-921-7700.

**AIRPORT REMARKS:** Attended continuously. Rwy 07-25 west 1300' only 25' wide. Glider ops in/ov arpt. Land to the east tkf to the west winds permitting. 100LL fuel avbl for emerg use only. Pedestrians, motor vehicles, deer and wildlife on and in/ov arpt. Unlimited vehicle use on arpt. Rwy West has +35' building 170' west of thld 30' left, +10' road 100' from thld centerline. +15' tree 150' from thld OB. -8' to -20' terrain off both sides of first 674' of Rwy 25 end. E-W rwy consists of +12 inch alfalfa vegetation during various times of the year. Rwy 07 has 40' trees and -10' to -20' terrain 20' right of rwy first 150'. Rwy 25 has +20' trees 300' from thld OB. Rwy 25 has 50' water tanks 900' from thld on extended centerline. +2' electric box 150' from thld 30' right. +10' road 100' from thld OB. Rwy E has +20' trees at thld 150' right of centerline, +10' trees 150' from thld OB.

**AIRPORT MANAGER:** 970-921-7700  
**COMMUNICATIONS:** CTAF/UNICOM 122.8

CONTINUED ON NEXT PAGE

## CONTINUED FROM PRECEDING PAGE

**CLEARANCE DELIVERY PHONE:** For CD ctc Denver ARTCC at 303-651-4257.

**RADIO AIDS TO NAVIGATION:** NOTAM FILE MTJ.

**MONTROSE (VH) (H) VORW/DME** 117.1 MTJ Chan 118 N38°30.39' W107°53.96' 033° 16.9 NM to fld.  
5713/12E. vDME unmonitored.

DME unusable:

011°-090° byd 26 NM blo 15,000'  
190°-250° byd 25 NM blo 15,000'

VOR unusable:

001°-167° byd 40 NM  
060°-090° byd 26 NM blo 16,000'  
167°-178° byd 50 NM  
168°-178° byd 40 NM blo 16,300'  
179°-251° byd 40 NM  
190°-250° byd 25 NM blo 15,000'  
252°-262° byd 40 NM blo 13,000'  
252°-262° byd 51 NM blo 15,500'  
252°-262° byd 72 NM  
263°-295° byd 40 NM  
313°-360° byd 40 NM

## CREEDE

**MINERAL CO MEML** (C24) 2 SSW UTC-7(-6DT) N37°49.33' W106°55.79'

8680 NOTAM FILE DEN

**RWY 07-25:** H6880X60 (ASPH) S-12.5

**RWY 07:** Thld dspclcd 188'.

**SERVICE:** FUEL 100LL, JET A

**AIRPORT REMARKS:** Unattended. Glider act and wildlife on and invof arpt. Mt all quad. Dep NE avoid overflight of trailers and homes, climb to +200 ft AGL on RCL bfr turn.

**AIRPORT MANAGER:** 719-658-2360

**COMMUNICATIONS:** CTAF 122.9

**CLEARANCE DELIVERY PHONE:** For CD ctc Denver ARTCC at 303-651-4257.

**RADIO AIDS TO NAVIGATION:** NOTAM FILE DEN.

**BLUE MESA (VH) (DH) VORW/DME** 114.9 HBU Chan 96 N38°27.13' W107°02.38' 158° 38.1 NM to fld.  
8740/14E.

DME unusable:

315°-325° byd 27 NM blo 17,500'

VOR unusable:

016°-026° byd 40 NM blo 17,500'  
027°-032° byd 40 NM  
033°-072° byd 40 NM blo 16,200'  
075°-085° byd 40 NM blo 16,000'  
075°-085° byd 58 NM  
086°-093° byd 40 NM  
098°-118° byd 40 NM  
119°-129° byd 40 NM blo 18,000'  
130°-187° byd 40 NM  
188°-198° byd 40 NM blo 18,000'  
199°-209° byd 40 NM  
210°-240° byd 40 NM blo 16,600'  
210°-240° byd 54 NM blo 18,000'  
210°-240° byd 59 NM blo 20,000'  
268°-274° byd 40 NM  
275°-285° byd 40 NM blo 14,000'  
275°-285° byd 50 NM  
286°-297° byd 40 NM blo 19,000'  
298°-015° byd 40 NM

**CUCHARA VALLEY AT LA VETA** (See LA VETA on page 353)